MYSORE DIVISION.

Dated 8th May 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 15th June 1931, for Restoring Chikyathanahalli Munigowdankere, Registered No. 698, Hunsur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty (Rs. 250) only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Chikyathanahalli Munigowdankere Registered No. 698, Hunsur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tendered rates will not be increased on any account.

10. Rates should be clearly quoted both in figures and words for each item of work.

11. Lumpsum estimate at per cent below or above sanctioned amount will not be accepted.

Abstract estimate for Restoring Chikyathanahalli Munigowdankere, Registered No. 698, Hunsur Taluk:—

Sl. No.	Items of work	Quantity	Unit	Rate in words	Rate in figures	Cost
	Bund.					Rs.
1	Jungle clearing	27	Grade			
2	Cutting grips in old bund	27	,,			
3	Earthwork to bund including watering and consolidating.	4,652	C.yd.			
4	Gravel backing to revetment ...	167	,,			
5	Turfiing	696·00	Sqr.			
6	Preparing and fixingn ew grade stones including dressing, figuring and painting.	27	No.			
7	Providing Index stones	27	,,			
8	Preparing and fixing gauge stone including cutting figures and painting.	1	,,			
9	Preparing and fixing B. M. stones including cutting figures and painting.	2	,,			
10	Preparing and fixing Date and Registered No. stone.	1	,,			
	Total to Bund ...	...				

Sl. No.	Items of work	Quantity	Unit	Rate in words	Rate in figures	Cost
	Breach filling.					Rs.
1	Earthwork excavation for puddle wall in breach and using the same for bund in rear.	73	C.yd.			
2	Removing silt in breach and using the same in rear.	241	,,			
3	Clay puddle wall in breach	187	,,			
4	Earthwork for breach with a mixture of clay and gravel including watering and consolidating.	1,316	,,			
5	Rough stone work dry with jelly packing	252	,,			
	Total for breach filling ...	...				
	Sluice.					
1	Reparing the masonry in the cistern, removing date trees and fixing jali wood plug with iron rod and locking arrangements.	Lump	sum Rs.			
	Waste weir extending the present one by 138'.					
1	Earthwork excavating and using the same to bund.	1,668	C.yd.			
2	Concrete in surki mortar	536	C.ft.			
3	Burnt brick in surki mortar	1,288	,,			
4	Burnt stone slabs 6" thick dressed and fixed.	316	S.ft.			
5	Plastering with surki mortar ...	16·24	Sqr.			
6	Rroug stone work dry with jelly packing	122	C.yd.			
7	Resetting old stone work dry ...	75	,,			
8	Plastering with cement	6·52	Sqr.			
	Total for wier ...	...				

K. NARAYANA IYENGAR,
Executive Engineer.

SPECIAL DIVISION, MYSORE.

Notice dated 15th May 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Division, Mysore, up to Saturday the 6th June 1931, till 12 noon for constructing a building for installation of the Dyeing and finishing plant, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1932.

2. The detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M. on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.